

GOVT. OF WEST BENGAL
OFFICE OF THE EXECUTIVE ENGINEER
MUNICIPAL ENGINEERING DIRECTORATE
BIRBHUM DIVISION, INDOOR STADIUM, SPORTS COMPLEX
RABINDRAPALLY, SURI, BIRBHUM. PIN-731101
Email: - eemedbir@gmail.com

Memo No. MED / BIR / 338 / C-05 / 2021

Date: 30.9.2021

CORRIGENDUM

Sub: - Fencing work at both side of 5Nos. Culverts/bridge at different Location at Moni kandar within Nalhati Municipality.

Ref: - I) Notice Inviting Tender No: 02 / 2021-22 (2nd call) dt- 29.09.2021
II) Tender ID No- 2021_MAD_345914_2, Date :- 29.09.2021


In the aforesaid Quotation following changes are made:-


Sl. No	Reference	In place of	Read as
1	2021_MAD_345914_2, Date :- 29.09.2021 ↓ NIT DOCUMENT ↓ SL NO-1	Name of Work:- Fencing work at both side of 5 Nos. Culverts/bridge at different Location at Kandar within Rampurhat Municipality.	Name of Work:- Fencing work at both side of 5Nos. Culverts/bridge at different Location at Moni kandar within Nalhati Municipality
2	2021_MAD_345914_2, Date :- 29.09.2021 ↓ NIT DOCUMENT ↓ SL NO-3	Estimate of Fencing work at both side of 5 Nos. Culverts/bridge at different Location at Kandar within Rampurhat Municipality.	Omitted

This is for general information to the all concern.

Copy forwarded for information to:-

1. The Secretary, M.E.Dte
2. The Chief Engineer, M.E.Dte
3. The Additional Chief Engineer (South), M.E.Dte
4. The Superintending Engineer, West Circle, M.E.Dte


30/09/2021
Executive Engineer
M.E.Dte. , Birbhum Division
Executive Engineer
Birbhum Division
A.E. Directorate, Deptt. of M.A
Govt. of West Bengal


30/09/2021
Executive Engineer
M.E.Dte. , Birbhum Division

Corrigendum

Page 1
Executive Engineer
Birbhum Division
A.E. Directorate, Deptt. of M.A
Govt. of West Bengal

Estimate for Fencing work at both side of 5Nos. Culverts/bridge at different Location at Monkandar within Nalhati Municipality.

Ref.	It. No.	Description of Item	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
PWD(bld.) Item No- 101/Pg- 777	1	Supplying, fitting, fixing, Chain link fencing of approved quality with R.C.C posts wooden posts or iron post, by means of galvanised "C" clips to grid of horizontal strands of galvanised high tensile spring steel wire of 12 S.W.G which have to be tensioned and fixed to the vertical posts by means of galvanised special clips, bolts and nuts etc. (The rate is exclusive of the cost of posts) 1) 50 mm. x 50 mm. x 8 g.	365.00	Sq.m	414.00	151110.00
PWD(bld.) Item No- 104(b)/Pg- 218	2	Fixing post of iron or precast concrete by digging hole in the ground (in all sorts of soil) and embedding the same by packing the hole with cement concrete (1:3:6) (with jhama khon. For Punilia, Bankura and Darjeeling Hill by Pakur Variety, Local Black Hard Stone & Bazree respectively) and finishing the top surface to regular shape (as directed) with 15 cm cement plaster (1:6) complete, including the cost of concrete, plaster etc. but excluding the cost of the post : (i) Average dia. of the hole 200 mm. to 300 mm. (a) Depth 450 mm. to 500 mm. [Cement 8 kg/No.]	80.00	Nos.	148.00	11840.00
PW(bld.) Schedule It-III, Pg- 99	3	M.S. structural works in columns, beams etc. with simple rolled structural members (e.g. joists, angle, channel sections conforming to IS: 226, IS: 808 & SP (6)- 1964 connected to one another with bracket, gussets, cleats as per design, direction of Engineer-in-charge complete including cutting to requisite shape and length, fabrication with necessary bolting, metal arc welding conforming to IS: 816- 1969 & IS: 1995 using electrodes of approved make and brand conforming to IS:814- 2004, haulage, hoisting and erection all complete. The rate includes the cost of rolled steel section, consumables such as electrodes, gas and hire charge of all tools and plants and labour required for the work including all incidental charges such as electricity charges, labour insurance charges etc. For structural members of specified sections weighing less than 22.5 Kg./m	2.75	MT	72603.00	199658.25
PWD(bld.) Item No- 1/Pg-200	4	(a) Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	870.00	Sq.m	29.00	25230.00
PWD(bld.) Item No- 2(b)(iv)/P g-200	5	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : (b) On steel or other metal surface : Withsuper gloss (hi-gloss) - (iv) Two coats (with any shade except white)	870.00	Sq.m	79.00	68730.00

(A) Sub Total = Rs. 4,56,568.25

(B) Add GST @ 12% on (A) 54,788.19

(C) Total of (A+B) = Rs. 5,11,356.44

(D) Add Cess @ 1% on (C) 5,113.56

(E) Add Contingency @ 3% on (C) = 15,340.69

5,31,810.70

Say, Rs. 531811.00

Rajendra Prasad Singh
Chairman
Nalhati Municipality

MAY BE VATTED

Amondal
22/7/21
H. Engineer
Birbhum Division

MAY BE VATTED

A.K. Das
22/07/21
Assistant Engineer
Birbhum Division

22/07/2021
Executive Engineer
Birbhum Division
A.E. Directorate, Dept. of M.A.
Sub-Assistant Engineer
Nalhati Municipality
Nalhati Birbhum