




Office of the
Executive Engineer,
Central Mechanical Division,
Urban Development & M.A. Department,
Government of West Bengal,
Nirman Bhavan,
Kolkata - 91,

Corrigendum

Tender Reference Number UD/e-NIQ/CMD/09/2017-18 OF EE CMD
Tender ID 2017_UDD_133684_1

Iron structure for machine installation as described in serial 01 of BOQ should follow the minimum following basic requirement-

- 1) At least 2 nos. Iron channel 75x40 mm of length 4 ft. To be grouted 150 mm in wall with 7 ft. Interval to form a structure.
- 2) 2 nos ISA of 50x50x4 mm of length 4 ft. To be grouted 150 mm in wall to facilitate machine installation with spacing as required in machine.
- 3) 1 inch flat with 3inch interval to be laid on the floor of the structure to facilitate work space for maintenance work.
- 4) Drawing should be submitted before taking up work but it should be kept in mind that sufficient space should be provided to facilitate work space for maintenance work.


Executive Engineer,
Central Mechanical Division

Memo No. 1063 (6)

Dated:30.10.2017

Copy forwarded for information & necessary action to:

- 1) The Special Engineer, Salt Lake Reclamation & Development Circle. U.D. Department
- 2) The S.D.O. Salt Lake Electrical Sub-Division.
- 3) Estimating section
- 4) Divisional Accounts Officer
- 5) Notice Board
- ✓ 6) Computer cell, Nagaryan.


Executive Engineer,
Central Mechanical Division